

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Providing SWM works at Kodigehalli in ward no 08 Kodigehalli

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	12.15	KSRB 2-2.1 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(a) / 2.3.5 (Page no -6, item no - 2.3)	Cum	322.92	Rupees Three Hundred Twenty Two and Ninety Two Paise Only
2	8.1	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS. Item No 2.15	Cum	2623.32	Rupees Two Thousand Six Hundred Twenty Three and Thirty Two Paise Only
3	4.05	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 465 cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth, including cost of all material, labour HOM Machinery curing complete as per specification, (Page. No. 13 Item No. 4.2	Cum	5609.52	Rupees Five Thousand Six Hundred Nine and Fifty Two Paise Only
4	5.4	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.12, I.No. 4.6 of PWD SR 2018-19)	Cum	5855.76	Rupees Five Thousand Eight Hundred Fifty Five and Seventy Six Paise Only
5	3	Providing heavy duty leaf shredder Machine (chopper Machine CMS - A)	No	200000	Rupees Two Hundred Thousand Only
6	10	BESCOM Deposit Charges	No	15000	Rupees Fifteen Thousand Only
7	35	Organic Leaf Composter Machine	Each	14500	Rupees Fourteen Thousand Five Hundred Only

DTS Approved

[Signature]
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))